



Description:

A severe storm in 2013 devastated the existing culverts on Ganong Drive and McCutcheon Lane. With the aid of the Federal Emergency Management Agency (FEMA), the Town was able to replace the existing corrugated metal culverts with new 3-sided concrete box culverts.

Special Notes of Interest:

The 3-sided box culverts were designed to be 1.25x the width of the Corners Brook ordinary high water mark. By designing to this standard, Corners Brook will be restored to a more natural stream flow, thus reducing erosion and improving aquatic habitat.

Owner: Town of Saranac
3662 NY-3, Saranac,
NY 12981

Construction Costs: \$659,000

Prime Contracts: One

Project Completion: November 2017

Funding Sources:

- FEMA

Regulatory Agencies:

- NYS DOT
- DEC
- APA
- ACOE
- FEMA
- County Highway Department

Services Performed:

X	Survey
X	Report
X	Design
X	Bidding
X	Construction

AES Team:

Wayne Ryan, PE - Principal In Charge
Evan Reil, LS - Land Surveyor
Joseph Bridgeman - Civil Engineer Technician
Mike Metcalf - Construction Manager
Tom Necrason - Resident Project Representative